



Genrock Construction and Mining Pty Ltd

P.O. Box 170
Carletonville
2515

Tel: (018) 786 1481
(018) 786 1482
Fax: (018) 786 1499

Genrock Mining

Area Representative: Johan Beytell
Cell: 082 828 1211

Marketing Manager: Etienne van Eeden
Cell: 082 417 7564

Pre-Stressing Units. Pump Equipment. Mining products.

GENROCK HAND PUMP S1

“THE PUMP THAT WILL NEVER LET YOU DOWN”

DESCRIPTION:

The unique Genrock nylon hand operated pump. Pumping all forms of liquid and pumpable grouts. Incorporated with a lightweight mixing tank and delivery assembly.

This unit is very easily dismantled for easy transport in difficult working places underground.

SPECIFICATIONS OF GENROCK HAND OPERATED PUMP S1

Overall length	70 cm
Overall height of pump	90 cm
Weight of pump	4.6 kg
Weight of container	9 kg
Total weight	13.6 kg
Mixer weight	2.6 kg
Output pressure	up to 10 bar
Capacity to mark	4 l & 8 l
Delivery hose	5 meters

The Genrock hand pump is designed to achieve cost-effective performance, particularly in areas where auxiliary services are limited or not available. The simple, robust design ensures that the unit is not only highly reliable but also easy to clean service and maintain. It is light in weight and easy to move, transport and set up.



ADVANTEGES OF GENROCK HAND PUMP

1. Does not support combustion.
2. The pump can easily be removed from the container.
3. The unit has minimum number of working parts.
4. Can be used in areas where air is not available.
5. No tools required to overhaul pump.
6. Unskilled labour can repair the pump.
7. Maximum cost on wearing parts is R120.00 per month.
8. Without abuse maintenance cost ± R15.00 per month.
9. Maintenance repair cost can be cut to 90%.
10. Capital cost for pump can be reduced to 50% of present cost.

MANAGING DIRECTOR: J.N. VAN DER MERWE